# ILC GDE Activities Update and Undulator Scheme Status

J. C. Sheppard SLAC November 8, 2006

November 8, 2006

J.C. Sheppard, SLAC

ILC GDE Activities Update, to date

December, 2005: Undulator Baseline Documentation – BCD

March, 2006: RDR Configuration: the undulator scheme

April, 2006: RDR Parts Inventory to Technical Systems for Costing

July, 2006: RDR Preliminary Costing Results (the Big Secret)

August-September, 2006: Cost comparisons between undulator and conventional schemes; central Injector layouts and initial costing activities.

September, 2006 GDE Decision: Undulator Scheme and Central Injector; ILC Positron Collaboration Meeting at RAL, UK

November, 2006 Valencia Meeting to discuss layout

ILC GDE Activities Update, thru end of calendar 2006

September, 2006: RDR Text Outlines (N. Phinney editor); no feedback

November, 2006: Valencia Meeting: RDR Text and Costs (???? rumors of short delay with appropriate rescoping of RDR deliverables....)15 pages for undulator scheme; not clear how alternatives are being handled.....deferred till Beijing, February, 2007

Valencia meeting to agree to RDR configuration and inventory

#### Layout of ILC Positron Source: December, 2005

- Photon production at 150 GeV electron energy
- ► K=1,  $\lambda$ =1 cm, 100 m long helical undulator
- Two e+ production stations (1 as backup) + KAS
- Pulsed OMD (shielded target)
- Keep alive auxiliary source is e+ side
- Timing Insert and Trombone in PML Extension



### Positron System Site Layout: July 2006



#### General Elevation View

### Positron System Site Layout Discussions: September, 2006



#### Layout of ILC Positron Source: November, 2006

- Photon production at 150 GeV electron energy
- $\triangleright$  K=1,  $\lambda$ =1 cm, 100 m long helical undulator
- (K=0.92, λ=1.15 cm, 100?? m long helical undulator, UK design under consideration)
- One e+ production station (no backup) + KAS
- Pulsed OMD (shielded target)
- Keep alive auxiliary source, 10% intensity



November 8, 2006

J.C. Sheppard, SLAC

# Positron System Site Layout Discussions: November, 2006 Central Injector Decision:

- Electron dr and a single positron dr in a single tunnel located at the center of the ILC site
- Two 14 mrad crossing angle IPs at a different elevation (~10-20 m) from dr's
- Positron production still at 150 GeV point in electron main linac
- e+ transport line reduced from 18.7 km to about 5 km
- Removal of timing insert (still need to do correct timing) and 2<sup>nd</sup> IP trombone
- Reduction of number of BPMs and correctors in 5 km transport line
- Deletion of redundant e+ production target
- Cost reductions thru hardware reduction
- ~30 km of low emittance, damped beam added to RTML systems

Ongoing discussions that have lives of their own November 8, 2006

## Positron System Site Layout Discussions: November, 2006

Impact to ongoing work for ILC Undulator Scheme:

No real changes to the technical challenges

No parameter changes

Reduction of transport lines

Rework of injection/extraction schemes

Still have same technical challenges and cost drivers

Work continues

Meeting with GDE Cost engineers in Valencia, closed session: primarily to settle on layout and protocols for information exchange

November 8, 2006