

France Contribution to the XFEL Project

Presentation of the **XFEL Cold Linac Consortium**

10 January 2008

S. Prat
CNRS/IN2P3/LAL
Orsay

O. Napoly
IRFU (ex DAPNIA)/SACM
CEA-Saclay

The XFEL Project


in short

XFEL: the accelerator

Final energy 17.5 GeV (instead of 20 GeV)

RF Gun + 1 cryomodule + 25 RF units (10 MW, 4 cryomodules, 32 cavities)


- + (1) x 4 x 8 x 12,5 MeV → 500 MeV
- + (2+1) x 4 x 8 x 23.6 MeV → 2 GeV
- + (20+1) x 4 x 8 x 23.6 MeV → 17.5 GeV



Total: 25 Klystrons, 101 modules, 808 Cavities
including 2 RF units (64 cavities) for spare

XFEL : Schedule

- We have the overall schedule promising first beam through the linac before end of 2013; this schedule can be used to determine earlier project milestones



XFEL: Work Packages

Group 1: Linac Cold Linac	01 RF System 04 SC Cavities 07 Frequency Tuner 11 Cold Magnets	02 Low Level RF 05 Power Coupler 08 Cold Vacuum	03 Acc. Modules 06 HOM Coupler 09 Strings
Group 2: Accelerator Subsystems	12 Warm Magnets 16 Lattice 19 Warm Vacuum	14 Injector 17 Stand. Beam Diagn. 20 Beam Dump	15 Bunch Compress. 18 Spec. Beam Diagn. Cold BPM
Group 3: Photon Beam Lines	21 Undulators 24 Photon Diagnostic 27 FEL Concepts	22 Hard Photons 25 Experiment Areas	23 Medium Photons 26 Detector Developmt
Group 4: Control and Operation	28 Control Systems 36 General Safety	29 Operability 38 Personnel Interlock	35 Radiation Safety 39 EM Interference
Group 5: Infrastructure	10 Module Test Facility 33 Tunnel Installation	13 Cryogenic 34 Utilities	32 Survey
Group 6: Site and Buildings	31 Site and Civil	37 Plan Approval	

XFEL Cold Linac : Accelerating Modules

Superconducting Cavity (23.4 MV/m)



Clean Room Assembly




8-Cavity string with RF Couplers



Cavity string under Cold mass





Vacuum vessel and cantilever



Cryomodule in tunnel


XFEL Cold Linac Consortium

- DESY, INFN, CEA and IN2P3 will be the major in-kind contributors of the XFEL Cold Linac components



Estimated distribution of the In-Kind contributions to the XFEL Cold Linac

XFEL Cold Linac Consortium



	Cryomodule Fabrication	Cryomodule Assembly	Cavities / couplers	Clean Room Assembly
DESY	25 %	-	50 % cavities	Participation to supervision
INFN	25 %	Participation to supervision	50 % cavities	-
CEA IRFU-Saclay	50 %	100 % + couplers/warm	-	100 % + couplers/cold
IN2P3 LAL-Orsay	-		100 % couplers	

Coarse grain distribution of In-Kind Funds and Responsibilities


- This distribution of responsibilities is approved by the XFEL project management, the “In Kind Review Committee” and the “International Steering Committee”

The XFEL Coupler Production

by LAL-Orsay


*In the frame of the French contribution
to XFEL project,*

*LAL is in charge of "in-kind"
delivery of 832 input couplers*



Input coupler on cryomodule

X-FEL coupler



3 Main difficulties:

- Industrial production of coupler parts
- Assembly in clean room
- RF conditioning

Expertise required from industry in the couplers production

EB welding

Vacuum brazing

TiN coating th. ~ 10nm

Precise geometrical tolerances

Surface finish and cleanliness



Cu plating: $10 < RRR < 100$



Motorized tuning

EN 1.4435

EN 1.4429

Special austenitic stainless steel

TIG welding

- + He leak rate $< 10^{-10}$ Pa.m³/s
- + Careful Handling with gloves
- + Assembly in clean room
- + RF Conditioning



1 - LAL conducted industrialization studies to clarify the mass production of couplers

Award of 3 contracts in March 06: ACCEL, e2v, TOSHIBA

System Design Review:

- functional analysis

Preliminary Design Review:

- feasibility of the manufacturing processes
- samples for parts and joining

Critical Design Review:

- detailed drawings
- organization of the mass production
- risks analysis
- samples of Cu plating and TiN coating

Final Project Review:

- deliver 2 prototypes
- volume manufacturing plan
- costs estimate for XFEL couplers

SDR



2006

2 full days for each review at each contractor

PDR



2007

CDR



2008

FPR



2 - LAL has gained experience in Assembly and Conditioning




← Test station at LAL, sized for 50 couplers / year:

- clean room with 2 zones:





- class 1000: wash and rinse
- classe 10: dry, bake, assemble

- RF Modulator and 5 MW Klystron

Project of Clean room layout for 200 couplers / year →



3 - LAL has been working several years to optimize the RF conditioning time




Now: Total duration for conditioning + tests → 40h / pair if OK


Scenario for couplers production - WP5 of XFEL project

Principles:


- 2 industrial contracts: each for 416 couplers + (n/2) spares
- Production and assembly in specific clean room at each industry
- Responsibility of industry includes RF conditioning
- RF conditioning: 1 single station at LAL



Necessary infrastructure at LAL for XFEL couplers



Conditioning station




40 m² Clean room for:

- dismantling warm & cold parts from test stand
- packing in double bags filled with N₂
- treatment of couplers which failed conditioning

Storage space:

- shelves for 200 couplers
- prepare to deliver batches to DAPNIA

WP5 Interface with Linac schedule



Number of couplers:

- for test cryomodules: 24
- for Linac: 808
- spares: n

***The XFEL Cryomodule Production
at CEA-Saclay***

Cryomodule Production Plant

Project motivation:

a **unique** cryomodule production plant is favored by the XFEL Management to save the cost of the Clean Room and Integration Halls.


CEA motivation:

Saclay will host this infrastructure in the pre-existing SATURNE hall complex, in synergy with

- a) moving the late 80's "MACSE" SCRF clean room




- b) SPIRAL2 SCRF needs.




Infrastructure requirement: 1 module/wk

© Accel Instrument GmbH



In case of technical problems, the module can be parked on redundant place.
working on other modules continues without interference

SYNERGIUM: Accelerator and Cryomagnetism




Saclay Infrastructure Layout

POS INSTALLATION 218

Bâtiment 126 Nord
200 m² + 300 m²

Bâtiment 124 Zone Salle Blanche
200 m² + 200 m²




Echelle SEPTEMBRE 2007

Bâtiment 126 Sud Storage
250 m²

XFEL Clean Room

Design finished.
Installation June 2008.
In operation beginning 2009.



Cryomodule Industrialization

Saclay will host the Production of the 101 Cryomodules, in collaboration with INFN and DESY.

The Production will be organized in three Work Packages

1. Fabrication of Cold Masses
2. Clean Room Assembly of Cavity Strings
3. Cryomodule Assembly

All three Work Packages will be subcontracted to Industries:


The Call for Tender Model is under discussion by the Cold Linac Consortium:

- One global vs. Three separate calls ?
- One vs. Two Industries for Cold Masses ?
- General problem of definition of the limits of responsibilities ?


The Industrial Solution retained will set the standard for future projects

Cryomodule Cold Mass (DESY definition)


Vacuum Vessel



Support and Return Pipe




Sliding Sleeve




Cryomodule Cold Mass with Cavities

module end group




module to module connection.



magnet package

beam position monitor

manual valve




cold mass with cavities, magnet / BPM, HOM abs. beam pipe, valve.

The Cold BPM



by CEA-Saclay

Re-entrant Cavity BPM



Re-entrant cavity BPM located at cryogenic temperature inside the cryomodule (ACC1).

Re-entrant cavity BPM installed in a warm section on the FLASH linac





Beam Calibration at FLASH BPM-ACC7

Beam is moved with one steerer.

Calculate for each steerer setting, the relative beam position in using a transfer matrix between steerer and BPM (magnets switched off to reduce errors and simplify calculation).

Average of 500 points for each steerer setting.



Calibration results from horizontal (left) and vertical (right) steering





Good linearity in a range ± 5 mm



**RMS resolution: ~ 4 μm on the Y channel
 ~ 8 μm on the X channel**

with 1 nC

Broader dynamic range with a 6 dB attenuator on each channel



Good linearity : ± 10 mm @ 0.8 nC
 ± 15 mm @ 0.45 nC


Resolution measurement:

correlation of the reading of one BPM in one plane against the readings of all other BPMs in the same plane (using linear regression).


Charge	Resolution Re-entrant	Resolution Re-entrant+ 6 dB attenuator
1.0 nC	$\sim 4 \mu\text{m}$	
0.8 nC		$\sim 12 \mu\text{m}$
0.5 nC	$\sim 11.8 \mu\text{m}$	$\sim 21 \mu\text{m}$
0.2 nC	$\sim 30.1 \mu\text{m}$	$\sim 55 \mu\text{m}$

Time Resolution at FLASH

	Damping Time cavity only	Time resolution cavity + electronics
BPM	9.4 ns	40 ns



RF signal measured at one pickup



100 bunches read by the re-entrant BPM

Possibility of bunch to bunch measurements

BPM Summary

High resolution re-entrant cavity BPM features:

- Effective in clean environment
- Operation at room and cryogenic temperature
- Large aperture of the beam pipe (78 mm)
- Position resolution around 4 μm measured with a measurement dynamic range around ± 5 mm
- Time resolution around 40 ns
- ~ 20 to 30 BPMs will be installed in the XFEL Linac.

This BPM is a good candidate for being installed in the ILC cryomodules