




# Main Linac Design




Chris Adolphsen  
GDE  
SLAC

April 6-7, 2006 MAC Review at FNAL

# Main Linac Design


- BCD distilled from Snowmass Working Group recommendations.
  - WG5 for the cavity package and cryomodule
  - WG2 for the rf system and cryomodule
- Major differences from 2001 Tesla TDR 500 GeV Design.
  - Higher gradient (31.5 MV/m instead of 23.4 MV/m) for cost savings.
  - Two tunnels (service and beam) instead of one for improved availability.
- GDE Linac Area Group is continuing to evolve design.

# ILC Linac RF Unit (1 of ~ 600)




Gradient = 31.5 MV/m  
Bunch Charge =  $2e^{10}$  e  
Rep Rate = 5 Hz  
# of Bunches = 2967  
Bunch Spacing = 337 ns  
Beam Current = 9.5 mA  
Input Power = 311 kW  
Fill Time = 565  $\mu$ s  
Train Length = 1000  $\mu$ s

# Relative Total Project Cost\* (TPC) -vs- Linac Gradient



\* TPC is for 500 GeV machine in US Options Study.

# 1.3 GHz TESLA Cavities




- ▶ For ILC, would accept only ‘vertically’ tested cavities (using CW rf without high power couplers) that achieve gradients  $> 35$  MV/m and  $Q > 8e9$  (discard or reprocess rejects).
- ▶ When installed in 8 cavity cryomodules, expect stable operation at an average gradient of 31.5 MV/m and  $Q = 1e10$  (rf system designed for 35 MV/m).
- ▶ Derating due to desire for overhead from quench limit, lower installed performance and limitations from using a common rf source.
- ▶ For a 1 TeV upgrade, expect average gradient = 36 MV/m,  $Q = 1e10$  for new cavities (the TDR 800 GeV design assumed 35 MV/m and  $Q > 5e9$ ).

# Achieved Gradients in Single and 9-Cell Cavities

- In recent years, single-cell cavity gradients approached fundamental limit:  $B_c * (\text{Grad} / B_{\text{surface}}) \sim 1800/41.5 \sim 43 \text{ MV/m}$  for Tesla-shape cavities.
- During past 2.5 years, DESY has produced 6 fully-dressed cavities with Gradients  $> 35 \text{ MV/m}$  and  $Q > 8e9$ . Yield for such cavities  $< 30\%$ .


Test Results for Dressed-Cavities that will be used in a '35 MV/m' Cryomodule




# Achieved Gradients in Tesla Test Facility (TTF) 8-Cavity Cryomodules (Cavities not Electro-Polished)

Diamonds and Error Bars = Range of Gradients Achieved in Individual CW Cavity Tests.

😊 = Average Gradient Achieved in Cryomodule






# High Gradient R&D: Low Loss (LL) and Re-Entrant (RE) Cells with a Lower $B_{\text{peak}}/E_{\text{acc}}$ Ratio





# Single Cell Results: $E_{acc} = 47 - 52$ MV/m




**Re-entrant**  
Fabricated  
at Cornell




**Low-Loss / Ichiro**

# Studies also underway using single or large grain Nb – could eliminate need for Electro-Polishing (EP)




BCP + 120C Baking

CEBAF Single cell Chinese Large Grain  $Q_0$  vs.  $E_{acc}$



# Tuning the Cavities


- Both slow (500 kHz over minutes) and fast (2.5 kHz during the 1.6 ms pulse) tuning required – achieve by compressing the cavity ( $\sim 1$  micron per 300 Hz).
- Want tuners located away from cavity ends to minimize cavity spacing.
- ‘Blade Tuner’ shown below. To date, have not achieved more than  $\sim 1$  kHz range of fast tuning. Final design for BCD not yet chosen.



# Powering the Cavities


- Power coupler design complicated by need for tunability ( $Q_{ext}$ ), windows and bellows.
- Baseline TTF3 design processed to 1 MW and tested up to 600 kW for 35 MV/m operation (1000 hours): long term reliability for required operation at 350 kW not known.

Coaxial Power Coupler




# RF Fill Dynamics

- Adjust  $Q_{ext}$  to match cavity impedance ( $R/Q_0 * Q_{ext}$ ) to the beam impedance (Gradient / Current) so zero reflected power during fill.
- For ILC,  $Q_{ext} = 4e6$  so cavity BW = 325 Hz ( $\Delta L = 1$  micron).
- Need to achieve  $< 0.1\%$  energy gain uniformity with LLRF system
  - Feedback to maintain constant 'sum of fields' in 24 cavities



# RF Distribution Math

(for 35 MV/m Max Operation)



$35 \text{ MV/m} * 9.5 \text{ mA} * 1.038 \text{ m} = 345 \text{ kW}$  (Cavity Input Power)


× 24 Cavities

× 1/.93 (Distribution Losses)

× 1/.89 (Tuning Overhead)

= 10.0 MW

# ILC Linac RF Unit (1 of ~ 600)



Gradient = 31.5 MV/m  
Bunch Charge =  $2e^{10}$  e  
Rep Rate = 5 Hz  
# of Bunches = 2967  
Bunch Spacing = 337 ns  
Beam Current = 9.5 mA  
Input Power = 311 kW  
Fill Time = 565  $\mu$ s  
Train Length = 1000  $\mu$ s

# Modulators


- **Baseline: Pulse Transformer**
  - 10 units have been built over 10 years, 3 by FNAL and 7 by industry.
  - 8 modulators in operation – no major reliability problems (DESY continuing to work with industry on improvements).
  - FNAL working on a more cost efficient and compact design, SLAC building new dual IGBT switch.
- **Alternative: Marx Generator**
  - Solid state, 1/n redundant modular design for inherent high availability, reliability.
  - Highly repetitive IGBT modules (90,000) cheap to manufacture.
  - Eliminating transformer saves size, weight and cost, improves energy efficiency.



# Modulators (115 kV, 135 A, 1.5 ms, 5 Hz)



Pulse Transformer Style




MARX MODULATOR - MECHANICAL DETAIL

(~ 2 m Long)

To generate pulse, an array of capacitors is slowly charged in parallel and then discharged in series using IGBT switches.



Will test full prototype in 2006

# Modulator Unit 1 vs. 600 Unit Avg. Production Cost Estimates



# Other Modulator R&D

- Three Marx SBIR Phase I proposals awarded in US.
- DTI Direct Switch due at end of 2006 for evaluation at SLAC.
- SNS High Voltage Converter Modulator being operated, optimized, evaluated at SLAC L-Band Test Facility.



# Low Level RF

---

## Proposal for Baseline Design

- LLRF systems for VUV-FEL and X-FEL should serve as baseline for LLRF for ILC. Same architecture is used as SNS, J-PARC, Cornell and others with smaller number of channels.
- Performance (Luminosity !) of ILC is strongly coupled to performance (field stab. and availability) of LLRF
  - Need high degree of automation
  - Beam based feedbacks
  - Build-in diagnostics
  - Extensive exception handling
- Requires assembly of several strong teams from regions

} Most of the work just started

# Klystrons

Baseline: 10 MW Multi-Beam Klystrons (MBKs) developed by three tube companies in collaboration with DESY



Thales



CPI



Toshiba


# Status of the 10 MW MBKs

- Thales: Four tubes produced, gun arcing problem occurred and seemed to be corrected in last two tubes after fixes applied (met spec). However, tubes recently developed other arcing problems above 8 MW. Thales to build two more without changes and two with changes after problem is better diagnosed.
- CPI: One tube built and factory tested to 10 MW at short pulse. At DESY with full pulse testing, it developed vacuum leak after 8.3 MW achieved – has been repaired and will be tested again.
- Toshiba: One tube built and achieved operation spec but developed arcing problems above 8 MW – being shipped to DESY for further evaluation.
- These are vertically mounted tubes – DESY will soon ask for bids on horizontally mounted tubes for XFEL (also needed for ILC).

# Alternative Tube Designs

## 10 MW Sheet Beam Klystron (SBK)


Parameters similar to  
10 MW MBK



SLAC

## 5 MW Inductive Output Tube (IOT)

Peak Output Power	5	MW (min)
Average Output Power	75	kW (min)
Beam Voltage	115	kV (nom)
Beam Current	62	A (nom)
Current per Beam	5.17	A (nom)
Number of Beams	12	---
Frequency	1300	MHz
1dB Bandwidth	4	MHz (min)
Gain	22	dB (min)
Efficiency	70	% (nom)



CPI

## Low Voltage 10 MW MBK

Voltage 65 kV  
Current 238A  
More beams

Perhaps use a Direct  
Switch Modulator

KEK



# Klystron Summary

- The 10 MW MBK is the baseline choice – continue to support tube companies to make them robust (DESY needs 35 for XFEL although will run at 5 MW).
- SLAC funding design of a 10 MW sheet-beam klystron (will take several years to develop).
- Backup 1: Thales 2104C 5 MW tube used at DESY and FNAL for testing – it appear reliable (in service for 30 years) but has lower efficiency compared to MBKs (42% vs 65%).
- Backup 2: With increased DOE funding next year, propose to contract tube companies to develop high efficiency, single-beam, 5 MW klystron.



# RF Distribution



Baseline choice is the waveguide system used at TTF, which includes off-the-shelf couplers, circulators and 3-stub tuners (phase control).



# Need more compact design



(Each Cavity Fed 350 kW, 1.5 msec Pulses at 5 Hz)

Two of ~ 16,000 Feeds




# And should consider simplifications

(circulators are ~ 1/3 of cost)



# Alternative Waveguide Distribution Schemes Being Considered by DESY



# Cryomodules


TTF Module	Installation date	Cold time [months]
CryoCap	Oct 96	50
M1	Mar 97	5
M1 rep.	Jan 98	12
M2	Sep 98	44
M3	Jun 99	35
M1*	Jun 02	30
MSS		8
M3*		19
M4	Apr 03	19
M5		19
M2*	Feb 04	16



# Cryomodule Design

## Relative to the TTF cryomodules


- Continue with 8 cavities per cryomodule based on experience and minimal cost savings if number increased (12 in TDR).
- Move quad / corrector / bpm package to center (from end) to improve stability.
- Increase some of cryogenic pipe sizes (similar to that proposed for the XFEL).
- Decrease cavity separation from 344 mm to 283 mm as proposed in the TDR.




# Beam-Related Design Issues

- **Optics / Tolerances / Operation similar to that in TDR:**
  - One quad per rf unit (three, 8-cavity cryomodules).
  - Few hundred micron installation tolerances for cavity, quad and BPM (demonstrated with TTF cryomodules).
  - Cavity BPM resolution of a few  $\mu\text{m}$  (should be achievable).
  - Use quad shunting and DFS tuning algorithms for dispersion control (need to better understanding systematic effects).
  - Assume beamline will follow Earth's curvature.
  - XFEL will serve as a benchmark although emittance much larger.
- **Alternatives for cost savings.**
  - Larger quad spacing at high energy end of the linac where wake and dispersion effects smaller.
  - Halve quad and bpm aperture to allow superferric quad and higher resolution BPMs (increases wakes by 10%).

# Quad / Corrector / BPM Package





ILC  
Proposal






# Vertical Quad Vibration at TTF

(ILC Goal:  $< 100$  nm uncorrelated rms motion  $> \sim 0.2$  Hz)



# Alternative Quad Location



# Cryogenic System

Assume static heat leaks based on TTF measurements instead of the smaller values assumed in the TDR





Figure 8.7.2: *Cryogenic unit.*


# Cryoplant Layout

For ILC 500, require 57 MW of AC power for Cryoplants



# Tunnel Layout

For baseline, developing deep underground (~100 m) layout with 4-5 m diameter tunnels spaced by 5 m.



# Summary

- Basic linac design complete: converging on details
  - Tradeoffs of operability, availability and cost.
- Major cost and technical risks
  - Producing cryomodules that meet design gradient at a reasonable cost (cost model still in development, XFEL will provide a reference, and will get new industry-based estimates).
  - Producing a robust 10 MW klystron.
- Potential Cost Savings
  - Adopt Marx Modulator
  - Use simpler rf distribution scheme
  - Have one tunnel although ‘the additional cost is marginal when considering the necessary overhead and equipment improvements to comply with reliability and safety issues.’
  - Reduce cavity aperture to 60 mm for 21% reduction in dynamic cryo-loading and 16% reduction in cavity fill time.