


# LICAS

Status and future plans  
Armin Reichhold



Warsaw  
University




# Overview

- Aims and measurement principle (reminder)
- Status:
  - Electronics and DAQ
  - Service Cars
  - Measurement Units
  - Measurement Cars
  - Reference Interferometers
  - FSI measurement results
  - LSM
  - Software and Simulations
  - DESY tunnel
- Future Plans
  - Short term
  - Long term


# Reminder of Aim

- Build a Rapid Tunnel Reference Surveyor (RTRS) to demonstrate feasibility of “LiCAS style” ILC survey
- RTRS prototype will operate in a test tunnel at DESY
- RTRS is aimed at the straight sections of the ILC

# RTRS concept




LiCAS technology for automated stake-out process



Reconstructed tunnel shapes (relative coordinates)







# Status of LiCAS

- LiCAS is in the final part of prototype RTRS production
- Shipment of service cars to DESY in 14 days
- Shipment of measurement units in 2 months
- All parts of the project (Electronics, Mechanics, LSM, FSI) are involved in end of series production or sub-system assembly, calibration and commissioning.
- I can only show some examples of electronics and mechanics status.


# Electronics Status

EuroTeV Meeting, Armin Reichold


- Custom Opto-detection & amplification, ADC & USB-DAQ for FSI (50 chan.) in final tests, some firmware still improving
- Readout for 12 LSM CCD cameras finished
- Trigger & clock distribution system finished
- RTRS propulsion control finished  
some software tuning remaining



opto-amplifier  
in custom rack




rack power supply



interlock and security switch unit 7

- Each measurement car has one service car
- Service car carries:
  - DAQ-electronics rack with PS, FSI readout, stepper motor control, temperature and pressure readout
  - DAQ-server with LSM framegrabber
  - propulsion units with slave controller
- One additional master car for central train control & lasers




CAD design of  
service car



- Oxford drive tests on 25m rail
- 3 service + 1 master car + 3 "dummy" measurement cars as loading
- Developed torque synchronisation software
- First three schemes tested
- Very close to complete





- Machined from single cast of multiply stress relieved Invar
- High precision machining of active element seats  $O(10 \mu\text{m})$
- CMM survey of the entire unit and sub-assemblies
- Unit under vacuum
- Optimised heat transfer paths from CCD's to surface
- Custom vac. fibre feedthroughs
- Design maxime:
  - Stability of active element positions
  - Machinability
  - Calibratability





# Measurement Unit production


EuroTeV Meeting, Armin Reichold



- Extremely tough material
- Machine in multiple steps to minimise distortions
- Very slow machining speed
- Very expensive tooling






- 3 Units built at DESY (finished)
- 6 DOF for position of measurement unit to:
  - Adjust to wall marker
  - Adjust to neighbouring cars
- Total of 12 stepper motors and stages controlled via CAN-bus
- Extremely rigid frame for:
  - Position repeatability
  - Vibration stability
- Mechanical decoupling from noise in service car
- Clamps to rail while measuring




# Measurement Cars\*

EuroTeV Meeting, Armin Reichold




- Provide length reference for FSI (OPD=10m bit longer than longest measurement)
  - Folded path to keep external dimension low
  - Absolute length calibration by measurement of frequency range of FSI scan through high accuracy, pre-calibrated acetylene absorption cell
- Must have long term stable length to  $O(10^{-7})$ 
  - Extremely rigid design for optical mounts
  - Fully stress relieved parts
  - Age the interferometer through many temperature cycles
- Must have temperature invariant length to  $O(10^{-8}/K)$ 
  - Evacuated optical cavity with Invar (SuperInvar) spacers
  - Expansion tuned using counter expanding AL parts of finely adjustable length
  - Good thermal contacts between all parts
  - Tuning of counter expansion length:
    - Stabilise temperature of one interferometer to  $O(0.3K)$
    - Sweep temperature of the other from  $+70C$  to  $-70C$
    - Measure length changes of the swinging interferometer wrt to the stabilised one and adjust length accordingly
- Must be verifiable
  - Use 4 Interferometers (2\*Invar, 2\*Super Invar) to get different systematics
  - Slightly different OPDS (8m and 10m)
  - One is on the train the other is off in a stabilised room
  - Frequently compare on-train with off train and Invar with Super Invar
  - Highly accurate calibrated temperature measurement system to keep monitoring length vs. temperature

# Reference Interferometers






- Using old Michelson style Ref. Interferometer
- Passive thermal shield, operates in air, no expansion compensation, steel table
- OPD measured over **25 min**
- No offline corrections for thermal expansion
- OPD =  $4.6999989 \pm 5.94 \times 10^{-7} \text{ m}$







	SPC-MI	APC-MI
Gradient	$1.96474 \pm 0.005161$	$1.97536 \pm 0.005546$
Intercept	$8.86788 \pm 7.5 \times 10^{-7}$	$8.83643 \pm 8.1 \times 10^{-7}$
RMS of residuals	$5.24735 \times 10^{-6}$	$5.63799 \times 10^{-6}$



- (a) OPD correlation between SPC-MI and APC-MI, 0.25mm stage displacement
- (b) Residuals of the linear fit to the correlation.
- Clear that we see common mode fluctuations in both interferometers

- Reference length variations
- OPD changes from
  - Temperature
  - pressure

	Value
Gradient	$1.00549 \pm 0.0003328$
Intercept	$-0.0801344 \pm 0.002951$
RMS of residuals	<u><math>6.65152 \times 10^{-7}</math></u> $\pm 4.42 \times 10^{-13}$




	SPC-MI	APC-MI
Gradient	$1.94716 \pm 0.004202$	$1.87703 \pm 0.009822$
Intercept	$8.86852 \pm 1.2 \times 10^{-7}$	$8.83708 \pm 2.8 \times 10^{-7}$
RMS of residuals	<u><math>8.21495 \times 10^{-7}</math></u>	$1.92007 \times 10^{-6}$
Spectral SNR	$42292 \pm 599$	$29425 \pm 523$



## Summary:

- Sub micron repeatability
- Now air refraction limited
- Absolute calibration to come shortly


- performance with evacuated reference & measurement interferometer should be much better.
- More potential if we start using phase information in spectral analysis as M-Phys thesis has shown in simulation



- measure temperature distribution on cameras in vacuum
- measure image distortions in vacuum by viewing 2D grating interference pattern
- result: camera works very well in vacuum due to very low power consumption and good mechanical structure
- Distortions below detection level (0.1 micron)



photograph of old LSM set-up with inlays  
of new components



new LSM with  
improved DAQ  
and stages

new reflector units  
with retro reflector  
and mirror for calibration

# Software Status

EuroTeV Meeting, Armin Reichold

- C++ DAQ software (90% tested)
- Spectral FSI analysis (works to sub micron levels but not yet automatic)
- LSM-Analysis (spectral filters, fits and noise suppression) completed
- LiCAS performance simulation complete

**Licac Data Acquisition**

File Hardware Script Tools Help

Creating Tab Controls...  
Creating Titles...  
Checking ADC Boards...  
Can't find NI Motion Board...  
Looking for NI-CAN...  
NI-CAN card not found....  
Looking for ESD CAN card..

ELMB Temp Setup 09:37:20, 01/30/06

No.	Script run list
0	Save Data Setup
1	ELMB read (ESD CAN)
2	ELMB Temp Setup

ELMB Temp Setup

Item	Action
6	Laser Trigger On / Off
7	Unavailable Melles Piezo Stage (NI CAN/Conf)
8	NI Stage(s) + ADC DAQ
9	Unavailable NI Stage(s) + ADC DAQ + Laser
10	Unavailable Melles Piezo Stage(s) + ADC DAQ
11	Unavailable NI Stage(s) + ADC DAQ + Temp + Laser
12	Unavailable Melles Piezo Stage(s) + ADC DAQ + Laser + Temp
13	Start of Loop
14	End of Loop
15	Pause
16	ELMB Temp Setup
17	Analysis Setup
18	ELMB read (ESD CAN)

No First Board  
N/A  
No Second Board  
N/A

LICAS  
OXFORDphysics

Clear Event Box Help

Script Function View Images

Temps/Tilt/Pres  
Sensor 1-16  
1:0.0000  
2:0.0000  
3:0.0000  
4:0.0000  
6:NaN  
7:NaN  
8:NaN  
9:NaN  
10:NaN  
11:NaN  
12:NaN  
13:NaN  
14:159.109

Temperatures  
Sensor 17-32  
17:167.887  
18:NaN  
19:NaN  
20:29.2001  
21:NaN  
22:77.1439  
23:NaN  
24:26.2543  
25:108.153  
26:67.0428  
27:NaN  
28:72.6759  
29:NaN

Sensor 1-32 selection checkboxes (all checked)

Unselect All Select All

Use Calibration Table Calibration Table


Test ELMB  
Addr: 1  
ELMB NET/Port  
Net 0  
Baud Rate: 125 Kbits  
(DAQ 0,1):Temp 1  
(DAQ 2,3):Temp 2  
(DAQ 4,5):Temp 3  
(DAQ 6,7):Temp 4

DAQ-GUI

Orsay, 15 May

- Currently dormant due to prototype production
- To be continued by current first year graduate student
- Interface from performance simulations to PLACET
- Preliminary beam based alignment study using LiCAS-aligned linac  
(this slide)

- Emittance growth vs. Quadrupole number
- Long range Licas survey errors only
- ongoing study



- 55m long
- stable walls
- air conditioning
- WLAN & LAN
- safety systems
  - air lock access
  - End stops
  - Laser interlocks
- Rail installed
- Power chain installed





# Short Term Future Plans

- LiCAS-I (funded from current LC-ABD program and embedded in EuroTeV)
  - = current 3-car prototype RTRS
  - complete production & assembly
  - install @ DESY May 06
  - operate @ DESY until end 06 (potential end 07)
  - data analysis
  - final results/publications by summer 07

# LiCAS Medium Term Future Plans

## (LiCAS-I upgrade)

- Design < Apr.07 (current grant)
- Construction < Jul. 08 (needs new funds)
- Small **upgrade of sensing unit**
  - **Carbon Fibre** → reduce weight → faster alignment
  - **compact** (potential for X-FEL)
- Reuses existing RTRS
- Electronics
  - dynamical train alignment during motion

# LiCAS Long Term Future Plans

## (LiCAS-II)

- Aims:
  - Add Damping Ring survey capability (CESR-TF)
  - Demonstrate LiCAS in real application (X-FEL)
- CESR-TF  $\leftrightarrow$  ILC-DR (time scale: early 2009? to start of ILC)
- DESY X-FEL  $\leftrightarrow$  ILC-Linac & BDS (time scale for survey: summer 2009 to end 2010)
- One RTRS (mech., DAQ, sensors, lasers)  $\leftrightarrow$  two configurations (straight, circular)
- Unclear how many units:  $4(\text{current}+1) < N < 6(\text{ILC specs})$
- potential for some fixed installations (HLS, LSM) at CESR-TF

The End