

LICAS


(Linear Collider Alignment and Survey)

Status "Highlights"

Armin Reichold



Warsaw
University



Overview

- Aims and measurement principle (reminder)
- Status:
 - Reference Interferometers
 - ~~FSI measurement technique~~
 - ~~FSI measurement results~~
 - ~~Electronics and DAQ~~
 - Service Cars and Drive Tests
 - DESY tunnel
 - Measurement Units
 - Measurement Cars
 - ~~LSM~~
 - ~~Software and Simulations~~
- ~~Future Plans~~
 - ~~Short term~~
 - ~~Long term~~

JAI @ Oxford



Cecilia Uribe started 1.8.05

Armin Reichold

Yanmei Han

Academic & post doc



Roy Wastie

Mark Jones

Mike Dawson

Ashley James electronic & DAQ

Elec. Tech.



Brian Ottewell

Tony Handford

Mech. Tech.

mechanic

student/ic (PhD)



John Green



Gregory Moss

John Dale started: 1.10.05

Project & Masters Students

Robert Apsimon
Peter Baker
Ken Chuang
Thomas Zlosnik
Simon Wilshin
Chris Glassman
James Robinson
Pauline Sliwa
Anna Lewis



Edward Botcherby



John Nixon

DESY



- Johannes Prenting
- Markus Schloesser
- Ernst-Otto Saemann
- Daniel Kaemtner


Warsaw



Bartek Szczygiel student


Gregorz Grzelak

- Problem (in a *peanut* shell):
 - ILC linac requires survey of components to 200 μm over distances of 600 m (vertical)
 - The survey should be “sufficiently fast”
 - Existing technology can not do this
- Aim
 - Develop a Rapid Tunnel Reference Surveyor (RTRS) to **demonstrate feasibility** of “LiCAS style” ILC survey
 - Build RTRS prototype and operate in a test tunnel at DESY as **demonstrator** and **R&D platform**
 - Current RTRS is aimed at the **straight sections** of the ILC



Measurement Principle

EuroTeV WP7 summary, Armin Reichold




Orsay, 15 May 06

Status of LiCAS

- All parts of the project (Electronics, Mechanics, LSM, FSI) are involved in end of series production or sub-system assembly, calibration.
- Shipment of service cars to DESY in 14 days
- Shipment of measurement units in 2 months
- I can only show “highlights” of electronics and mechanics status.

Reference Interferometers




vacuum vessel (shown semi transparent)

- Passive thermal shield around vac. chamber
- Thermal expansion tuning using temperature swing from +70 to -70 C
- Vibration damped mounts
- Aged through thermal cycles
- 16 accurately calibrated and aged temperature sensors
- Lots of tools for optimising mirror alignment
- Build 4 interferometers to study systematics



- Using old Michelson style Ref. Interferometer
- Passive thermal shield, operates in air, no expansion compensation, steel table
- OPD measured over **25 min**
- No offline corrections for thermal expansion
- OPD = $4.6999989 \pm 5.94 \times 10^{-7} \text{ m}$
- This is sufficiently sensitive
- Expect big improvements from new reference interferometers




- Oxford drive tests on 25m rail
- 3 service + 1 master car + 3 “dummy” measurement cars as pay load
- Developed torque synchronisation software
- Three schemes tested
- A week to complete



- 55m long
- stable walls
- air conditioning
- WLAN & LAN
- safety systems
 - air lock access
 - End stops
 - Laser interlocks
- Rail installed
- Power chain installed





- Design maxime:
 - **Stability** of active element positions and OPDs
 - **Calibratability**
 - Machinability
- Stability:
 - Unit under **vacuum**
 - Machined from single cast of multiply **stress relieved Invar**
 - Optimised **heat transfer** paths from CCD's to surface
- Calibratability
 - **High precision** machining of active element seats $O(10 \mu\text{m})$
 - CMM survey of the entire unit and sub-assemblies





Measurement Unit production

EuroTeV WP7 summary, Armin Reichold




- Extremely tough material
- Machine in multiple steps to minimise distortions
- Very slow machining speed
- Very expensive tooling




Measurement Cars*


EuroTeV WP7 summary, Armin Reichold



down
vac.
tube




from
tunnel
side



rapid
prototype of
measurement
unit


from
tunnel onto
measurement unit



from
wall
side

- Currently dormant due to prototype production
- To be continued by current first year graduate student
- Interface from performance simulations to PLACET
- Preliminary beam based alignment study using LiCAS-aligned linac
(this slide)

- Emittance growth vs. Quadrupole number
- Long range Licas survey errors only
- ongoing study







The End

Backup Slides

Electronics Status

EuroTeV WP7 summary, Armin Reichold


- Custom Opto-detection & amplification, ADC & USB-DAQ for FSI (50 chan.) in final tests, some firmware still improving
- Readout for 12 LSM CCD cameras finished
- Trigger & clock distribution system finished
- RTRS propulsion control finished
some software tuning remaining



interlock and security switch unit₁₈


- Provide length reference for FSI (OPD=10m bit longer than longest measurement)
 - Folded path to keep external dimension low
 - Absolute length calibration by measurement of frequency range of FSI scan through high accuracy, pre-calibrated acetylene absorption cell
- Must have long term stable length to $O(10^{-7})$
 - Extremely rigid design for optical mounts
 - Fully stress relieved parts
 - Age the interferometer through many temperature cycles
- Must have temperature invariant length to $O(10^{-8}/K)$
 - Evacuated optical cavity with Invar (SuperInvar) spacers
 - Expansion tuned using counter expanding AL parts of finely adjustable length
 - Good thermal contacts between all parts
 - Tuning of counter expansion length:
 - Stabilise temperature of one interferometer to $O(0.3K)$
 - Sweep temperature of the other from +70C to -70C
 - Measure length changes of the swinging interferometer wrt to the stabilised one and adjust length accordingly
- Must be verifiable
 - Use 4 Interferometers (2*Invar, 2*Super Invar) to get different systematics
 - Slightly different OPDS (8m and 10m)
 - One is on the train the other is off in a stabilised room
 - Frequently compare on-train with off train and Invar with Super Invar
 - Highly accurate calibrated temperature measurement system to keep monitoring length vs. temperature

- Each measurement car has one service car
- Service car carries:
 - DAQ-electronics rack with PS, FSI readout, stepper motor control, temperature and pressure readout
 - DAQ-server with LSM framegrabber
 - propulsion units with slave controller
- One additional master car for central train control & lasers






CAD design of
service car

- 3 Units built at DESY (finished)
- 6 DOF for position of measurement unit to:
 - Adjust to wall marker
 - Adjust to neighbouring cars
- Total of 12 stepper motors and stages controlled via CAN-bus
- Extremely rigid frame for:
 - Position repeatability
 - Vibration stability
- Mechanical decoupling from noise in service car
- Clamps to rail while measuring





	SPC-MI	APC-MI
Gradient	1.96474 ± 0.005161	1.97536 ± 0.005546
Intercept	$8.86788 \pm 7.5 \times 10^{-7}$	$8.83643 \pm 8.1 \times 10^{-7}$
RMS of residuals	5.24735×10^{-6}	5.63799×10^{-6}



- (a) OPD correlation between SPC-MI and APC-MI, 0.25mm stage displacement
- (b) Residuals of the linear fit to the correlation.
- Clear that we see common mode fluctuations in both interferometers

- Reference length variations
- OPD changes from
 - Temperature
 - pressure

	Value
Gradient	1.00549 ± 0.0003328
Intercept	-0.0801344 ± 0.002951
RMS of residuals	<u>6.65152×10^{-7}</u> $\pm 4.42 \times 10^{-13}$




	SPC-MI	APC-MI
Gradient	1.94716 ± 0.004202	1.87703 ± 0.009822
Intercept	$8.86852 \pm 1.2 \times 10^{-7}$	$8.83708 \pm 2.8 \times 10^{-7}$
RMS of residuals	<u>8.21495×10^{-7}</u>	1.92007×10^{-6}
Spectral SNR	42292 ± 599	29425 ± 523

Summary:



- Sub micron repeatability
- Now air refraction limited
- Absolute calibration to come shortly

- performance with evacuated reference & measurement interferometer should be much better.
- More potential if we start using phase information in spectral analysis as M-Phys thesis has shown in simulation




LSM camera vacuum test stand EuroTeV WP7 summary, Armin Reichold

- measure temperature distribution on cameras in vacuum
- measure image distortions in vacuum by viewing 2D grating interference pattern
- result: camera works very well in vacuum due to very low power consumption and good mechanical structure
- Distortions below detection level (0.1 micron)



photograph of old LSM set-up with inlays
of new components



new LSM with
improved DAQ
and stages

new reflector units
with retro reflector
and mirror for calibration

Software Status

EuroTeV WP7 summary, Armin Reichold

- C++ DAQ software (90% tested)
- Spectral FSI analysis (works to sub micron levels but not yet automatic)
- LSM-Analysis (spectral filters, fits and noise suppression) completed
- LiCAS performance simulation complete

Licas Data Acquisition

File Hardware Script Tools Help

Creating Tab Controls...
Creating Titles...
Checking ADC Boards...
Can't find NI Motion Board...
Looking for NI-CAN...
NI-CAN card not found....
Looking for ESD CAN card..

ELMB Temp Setup 09:37:20, 01/30/06

No.	Script run list
0	Save Data Setup
1	ELMB read (ESD CAN)
2	ELMB Temp Setup

ELMB Temp Setup

Item	Action
6	Laser Trigger On / Off
7	Unavailable Melles Piezo Stage (NI CAN/Conf)
8	NI Stage(s) + ADC DAQ
9	Unavailable NI Stage(s) + ADC DAQ + Laser
10	Unavailable Melles Piezo Stage(s) + ADC DAQ
11	Unavailable NI Stage(s) + ADC DAQ + Temp + Laser
12	Unavailable Melles Piezo Stage(s) + ADC DAQ + Laser + Temp
13	Start of Loop
14	End of Loop
15	Pause
16	ELMB Temp Setup
17	Analysis Setup
18	ELMB read (ESD CAN)

No First Board
N/A
No Second Board
N/A

LICAS
OXFORDphysics

Clear Event Box Help

Script Function View Images

Temps/Tilt/Pres
Sensor 1-16
1:0.0000
2:0.0000
3:0.0000
4:0.0000
6:NaN
7:NaN
8:NaN
9:NaN
10:NaN
11:NaN
12:NaN
13:NaN
14:159.109

Temperatures
Sensor 17-32
17:167.887
18:NaN
19:NaN
20:29.2001
21:NaN
22:77.1439
23:NaN
24:26.2543
25:108.153
26:67.0428
27:NaN
28:72.6759
29:NaN

Test ELMB
Addr: 1
ELMB NET/Port
Net 0
Baud Rate:
125 Kbits
(DAQ 0,1):Temp 1
(DAQ 2,3):Temp 2
(DAQ 4,5):Temp 3
(DAQ 6,7):Temp 4

DAQ-GUI

Orsay, 15 May

Short Term Future Plans

- LiCAS-I (funded from current LC-ABD program and embedded in EuroTeV)
 - = current 3-car prototype RTRS
 - complete production & assembly
 - install @ DESY May 06
 - operate @ DESY until end 06 (potential end 07)
 - data analysis
 - final results/publications by summer 07

LiCAS Medium Term Future Plans

(LiCAS-I upgrade)

- Design < Apr.07 (current grant)
- Construction < Jul. 08 (needs new funds)
- Small **upgrade of sensing unit**
 - **Carbon Fibre** → reduce weight → faster alignment
 - **compact** (potential for X-FEL)
- Reuses existing RTRS
- Electronics
 - dynamical train alignment during motion

LiCAS Long Term Future Plans

(LiCAS-II)

- Aims:
 - Add Damping Ring survey capability (CESR-TF)
 - Demonstrate LiCAS in real application (X-FEL)
- CESR-TF \leftrightarrow ILC-DR (time scale: early 2009? to start of ILC)
- DESY X-FEL \leftrightarrow ILC-Linac & BDS (time scale for survey: summer 2009 to end 2010)
- One RTRS (mech., DAQ, sensors, lasers) \leftrightarrow two configurations (straight, circular)
- Unclear how many units: $4(\text{current}+1) < N < 6(\text{ILC specs})$
- potential for some fixed installations (HLS, LSM) at CESR-TF