


CALICE Collaboration

Test Beam Status and Plans



Andy White

University of Texas at Arlington
(with much help from Felix Sefkow et al.! !)

Vancouver ALCPG, July 2006

Overview

- Motivation and technologies
- First Electromagnetic Calorimeter results
(from DESY)
- AHCAL: Hadronic 1m³ Calorimeter preparation
- CERN Test Beam Area
- Installation and test preparation
- The first week's news !
- CERN schedule/modules/goals
- Fermilab Test Beam program




Testbeam start-up at CERN

Felix Sefkow
July 14, 2006


Testbeam programme

- Calorimetry at the ILC
 - Need 2x better resolution
 - High granularity for individual particle reconstruction
- Physics:
 - Structure of hadron showers
 - Validation of simulation
 - Development of particle flow algorithms
- Technology
 - Establish compact SiW technology
 - gain large scale, long-term experience with a SiPM / RPC / GEM readout detector
- Running at CERN and FNAL from July 2006 on



CALICE ECal

- 130T of tungsten
- An octagonal geometry
- A high level of density
(20-40 layers, 24X0 in ~170mm)



- No large area of dead zone
- All modules are identical (Tungsten wrapped by Cfi)
- The detector slabs would be tested before assembling

CALICE - ECAL



Ewha Univ., Sungyunkwan Univ.,
Kangnung NU , Yonsei Univ.



LAL,LLR,LPC-Ct, LPSC, PICM




ITEP,IHEP, MSU




Prague (IP-ascr)









Imp. Coll, UCL, Cambridge
Birmingham, Manchester,RAL,
RHUL



The ECAL prototype




**9720 channels in 18 cm^3
for this prototype**




**DAQ
(UK)**

ECAL: first testbeam results



ECAL: first testbeam results



Transverse profile (w.r.t. barycentre)






HCAL testbeam prototype


- Scintillator HCAL construction at DESY
 - Mechanics
 - 1 cubic meter stack, cassettes, calibration light system
 - Assembly (with colleagues from ITEP, LPI, MEPHI)
 - FE electronics
 - With ASICs from LAL
 - Integration
 - 8000 Scintillator tiles and SiPMs (ITEP and MEPHI)
 - Calibration electronics (Prague)
 - DAQ (UK groups)
 - Tail catcher (Northern Illinois)



Commissioning at DESY



Cosmics set up
1x1 m² trigger plates
in coincidence
requires >3 modules
for telescopic cuts
analysis





Commissioning at DESY




HCAL test results

FE 0 chip 0 chan 13 hist



- From test bench to multi-channel system

Run 201353 - LED 2 - SER013, Slot 12, FE3 - Entries vs. ADC channels






HCAL test results

Run 220124 Event 2630

Time: 20:03:03:734:556 Fri May 5 2006

DaqEvent info ...



Tail Catcher (NIU)


The absorber has 8 layers of 2 cm thick and 8 layers of 10 cm thick steel.

Length is 142 cm.

Height is 109 cm.

Weight is about 10 tons.


TCMT has 16 cassettes with about $1 \times 1 \text{ m}^2$ active area, made from 5 cm extruded scintillator strips in alternating x-y orientation.



- All elements of the readout chain were fully tested, including common readout with AHCAL and electron beam test at DESY in November 2005.


Tail Catcher (NIU)

Beam Test at Fermilab in February 2006



Tail Catcher (NIU)

Response to 120 GeV/c Protons



CERN SPS North Area

Accelerator chain of CERN (operating)

SPS Test Beams

Up to 400 GeV

(closed)



n-ToF



p

\bar{p} (antiproton)
ion
neutrons

proton/antiproton conversion
neutrinos

p (proton)
ion
neutrons

LINAC

p


ions

BOOSTER

ISOLDE

AD Antiproton Decelerator
PS Proton Synchrotron
SPS Super Proton Synchrotron

LHC Large Hadron Collider
n-ToF Neutrons Time of Flight
CNGS Cern Neutrinos Grand Sasso



We are
here

*H6 beam,
Up to 15 GeV
area H6b*

PS Test Beams

Mechanical installation at CERN




HCAL, common DAQ

- HCAL looks like a real calorimeter for the first time



common DAQ: ADCs, VME



Overview, beam instrumentation





First week (July 3-7) Summary

- Monday: mechanical installation of ECAL, HCAL and racks, power
- Tuesday: DAQ tests, voltage supply, cable supports, first channels r/o
- Wednesday: DCs installed, full detector cabled and read out
- Thursday: trigger counters, r/o debugging, first LED signals seen
- Friday: Gigabit switch installed
- Already now: a fantastic success
 - See <http://www-flc.desy.de/hcal/cerntestbeam/>




First week summary




Analysis feedback

- Data transfer to DESY dCache
- using GRID tools



Preliminary testbeam schedule

- Draft schedule for CERN North Area beam line H6
- 3x main user
- Parasitic muon running
- SPS: smooth start-up after major repair
 - First beams in exp areas next week
 - Physics starts July 24th





Equipment

- ECAL: 27 of 30 layers in central part, almost full depth
- HCAL: 15 layers, every 2nd gap in 3.5λ , 25-30 in October
- TCMT: 50% of channels, first (fine) section (1λ)






Goals

- "CALICE ECAL":
 - 6-50 GeV electrons and pions
 - ECAL: data MC comparisons
 - HCAL: establish detector system and calibration
- "CALICE HCAL":
 - 6-100 GeV electrons and pions (+, -)
 - HCAL: First coarse data MC comparisons with HCAL only
 - TCMT: establish system and calibration
- "CALICE combined":
 - 6-100 GeV electrons and pions (+,-)
 - ECAL + HCAL + TCMT: data MC comparisons
 - Possibly some HCAL standalone with more layers and inclined incidence



Outlook





Outlook

Fermilab Test Beam - the next step!

(see next talk by Jose Repond)

- Move of ECal, AHCAL and TCMT from CERN to FNAL
- Repeat some of the CERN electron, hadron running
- Extend to low energy (1-5 GeV) running
- Stand alone tests with RPC 1m³ and GEM 1m³ DHCAL
- Comparison of AHCAL and DHCAL(s)
- Combination HCal \oplus ECal running
- Tagged protons, anti-protons, neutrons ??