



# Installation Systems

---

## Per-Unit Equipment Installation Handling Basis - Labor & Cost Add to Normal Labor & Cost in Restricted Tunnel Access Areas

Unit Weight		Labor	Units	Unit Labor	Unit Labor	2006 \$US Cost Basis		
Lbs.	Kg.	Hours		Hours per Lb.	Hours per Kg.	Labor Cost	Total Cost w/O&P	Total Cost w/O&P per Lb.
200	91	5.93	Each	0.0296	0.0652	\$315.00	\$470.00	\$2.35
500	227	8.00	Each	0.0160	0.0352	\$425.00	\$635.00	\$1.27
700	318	10.00	Each	0.0143	0.0314	\$535.00	\$795.00	\$1.14
1000	455	13.33	Each	0.0133	0.0293	\$710.00	\$1,050.00	\$1.05
2000	909	24.00	Each	0.0120	0.0264	\$1,275.00	\$1,900.00	\$0.95
3000	1364	32.00	Each	0.0107	0.0235	\$1,725.00	\$2,550.00	\$0.85
4000	1818	40.00	Each	0.0100	0.0220	\$2,125.00	\$3,175.00	\$0.79
5000	2273	48.00	Each	0.0096	0.0211	\$2,575.00	\$3,800.00	\$0.76

*( Draft 27 JUN 06 )*

---