EUDET in FCAL

Wolfgang Lohmann



VINCA, Belgrade Univ. of Colorado, Boulder, BNL, Brookhaven, AGH Univ., INP & Jagiell. Univ. Cracow, JINR, Dubna, NCPHEP, Minsk, FZU, Prague, IHEP, Protvino, TAU, Tel Aviv,

see: PRC R&D 01/02 (2002)


Instrumentation of the very forward region of the ILC detector

Participants of EUDET:

AGH Univ., INP & Jagiell. Univ. Cracow FZU, Prague, TAU, Tel Aviv, DESY, Zeuthen


JINR applied for being associated

DESY




Laser Positioning System

XYZ displacement measurement with two beams



Proposed setup with two beams and prism splitter: Design and construction.




Laser Positioning System, Details

New lasers with aspherical lenses – better spot – estimated cost of 1000 € (to be ordered)
Beam splitter with half transparent mirror – designed – suspended for the next year (~1200 €)
Improvement of algorithm to determine centre of two spots – cost of 500 € (temporary staff)
Prototype – in progress
Independent measurement of XYZ translations – Renishaw industrial system (0.1 µm resolution) – bought (900 €) and PC control card ordered (700 €)

Sensor Design and Test Facilities


- Study of the performance with large area sensors with ionising particles
- Design of large area sensor planes, proof of mechanical accuracy, electrical features, response at the edges

Test facilities (prob. stations, current and capacitance measurement) under installation in Zeuthen and Tel Aviv




Production placed via JINR Dubna

Test Beam Equipment



sensor box (I_{Dia}, T_{Dia}, HV)

Used for Irradiation Tests at DALINAC










Beam Area: Equipment



- Sensor holder

I-V conversion



Power supplies and monitoring




Surveillance from control room

Readout Electronics

 Read-out electronics for test-beam measurements

Test measurements with the LAL FLC-phy 3, one chip instrumented and running, results for Munich WS

 Design of an electronics matching the accelerator needs: no progress so far.



First steps are done:

- Test beam equipment partially available and running, completion is ongoing
- Laser alignment 'proof of principle experiment' under construction
- Test facilities for sensors in Zeuthen and Tel Aviv; Zeuthen will be upgraded, Tel Aviv started to collect equipment
- Read-out electronics: Phys-3 chip under test